



GENERAL NOTES:

- 1) 4000 PSI CONCRETE SHALL BE USED THROUGHOUT THE CURB.
- 2) EXPANSION JOINTS SHALL BE INSTALLED AT 30' INTERVALS USING PRECUT JOINT MATERIAL TEMPLATES.
- 3) SCORE JOINTS SHALL BE MADE AT 10' INTERVALS.
- 4) A 1/2" EXPANSION JOINT SHALL BE USED WHERE CURB ABUTTS CONCRETE PAVEMENT.
- 5) THE CURB SHALL BE PLACED INSIDE THE EDGE OF ASPHALT TO ALLOW PROPER INSTALLATION BY THE CURBING MACHINE.
- 6) HORIZONTAL REBAR TO BE NO. 3 AND VERTICAL REBAR TO BE NO. 5

REVISION		
ITEM NO.	DESCRIPTION OF CHANGE	APPROVAL DATE

TOWN OF COLLIERVILLE  
TOP SET CURB

TOC-509