



SECTION A-A

**NOTES:**

1. CURB IS TO BE REMOVED AND REPLACED A MINIMUM OF 12" EACH SIDE OF DRAIN OPENING.
2. CONCRETE SHALL BE 4,000 PSI LIMESTONE
3. REPLACE FULL SIDEWALK PANEL

REVISION		
ITEM NO.	DESCRIPTION OF CHANGE	APPROVAL DATE

TOWN OF COLLIERVILLE

SIDEWALK DRAIN DETAIL

SCALE: NONE

TOC-228