



NOTES

1. PRE-CUT EXP. JOINTS MATERIAL SHALL BE USED IN ALL EXP. JOINTS.
2. DUMMY JOINTS SHALL BE INSTALLED AT 10 FT. INTERVALS, MAXIMUM.
3. EXP. JOINTS SHALL BE INSTALLED AT 30 FT., MAXIMUM.
4. EXP. JOINTS SHALL BE INSTALLED AT ENDS OF RADIUS.
5. EXP. JOINTS SHALL BE LOCATED A MAXIMUM OF 10 FT. FROM INLET STRUCTURES.
6. CONCRETE SHALL BE 4000 PSI.

REVISION		
ITEM NO.	DESCRIPTION OF CHANGE	APPROVAL DATE

**TOWN OF COLLIERVILLE
VALLEY CURB AND GUTTER**

TOC-507