

**SECTION 01520**  
**CONSTRUCTION AIDS**

**PART 1 GENERAL**

1.01 REQUIREMENTS INCLUDED

- A. Furnish, install and maintain required construction aids, remove on completion of Work.

1.02 RELATED REQUIREMENTS

- A. Section 01010: Summary of Work

**PART 2 PRODUCTS**

2.01 MATERIALS, GENERAL

- A. Materials may be new or used, suitable for the intended purpose, but must not violate requirements of applicable codes and standards.

2.02 CONSTRUCTION AIDS

- A. Provide construction aids and equipment required by personnel and to facilitate execution of the Work: Scaffolds, staging ladders, stairs, ramps, runways, platforms, railings, hoists, cranes, chutes and other such facilities and equipment.

**PART 3 EXECUTION**

3.01 PREPARATION

- A. Consult with Engineer, review site conditions and factors which affect construction procedures and construction aids, including adjacent properties and public facilities which may be affected by execution of the Work.

3.02 GENERAL

- A. Comply with applicable requirements specified in sections of Divisions 2 through 16.
- B. Relocate construction aids as required by progress of construction, by storage or work requirements, and to accommodate legitimate requirements of Owner and other contractors employed at the site.

3.03 REMOVAL

- A. Completely remove temporary materials, equipment and services:

1. When construction needs can be met by use of permanent construction.
  2. At completion of Project.
- B. Clean, repair damage caused by installation or by use of temporary facilities.
1. Remove foundations and underground installations for construction aids.
  2. Grade areas of site affected by temporary installations to required elevations and slopes, and clean the area.
- C. Restore existing facilities used for temporary purposes to specified, or to original, condition.
- D. Restore permanent facilities, if any, used for temporary purposes to specified condition.

END OF SECTION